

MISCELLANEOUS WARNING , INFORMATORY AND REGULATORY SIGNS FOR ROAD WORKS



7001
Road works or temporary obstruction on carriageway ahead

Line painting

7001-1
Nature of road works (bespoke)

M1 Northbound

7001-2
Location of road works immediately ahead on route indicated (bespoke)

WORKFORCE IN ROAD SLOW

7001-3
Vehicular traffic should proceed slowly owing to workforce in road

Night-time works 14 July to 26 July Expect delays

7002-1
Dates when road works are to take place (bespoke)

Major road works on M25 between J6 and J13 Delays possible

7002-1 V
Major road works at a specified location ahead (bespoke)

HIGHWAYS AGENCY Work starts here 24 May for 3 weeks Delays possible

7003-1
Starting date and duration of road works (bespoke)

Delays possible until Mar 04 1 mile

7005
Delays possible for specified period owing to road works (bespoke)

Sorry for any delay End HIGHWAYS AGENCY

7006
End of road works & of any temporary restrictions (bespoke)

Riversford Water Company PLC WATER MAIN RENEWAL Completion expected September 2008 Contractor - N E Samson Ltd Emergency Telephone 020 7123 4567 Sorry for any inconvenience

7008
Nature of street works giving employer and contractor details



7009
Loose chippings on road ahead

SLOW WET TAR

7010-1
Vehicular traffic should proceed slowly due to temporary hazard

TEMPORARY ROAD SURFACE

7010-1 V2
Vehicular traffic should proceed slowly due to temporary hazard

RAMP AHEAD

7010-1 V3A
Vehicular traffic should proceed slowly due to temporary hazard

ROAD CLOSED

7010-1 V4
Vehicular traffic should proceed slowly due to temporary hazard

WHEN RED LIGHT SHOWS WAIT HERE

7011
Point beyond which traffic should not proceed

3-WAY CONTROL WAIT HERE UNTIL GREEN LIGHT SHOWS

7011-1
Same as 7011 where there is a road junction

NO ROAD MARKINGS FOR 2 MILES

7012
Temporary absence of road markings over distance indicated (bespoke)

NO ROAD MARKINGS

7012 V3
Temporary absence of road markings

RAMP

7013
Temporary sudden change in carriage way surface

NEW ROUNDABOUT AHEAD

7014
Permanent change in road layout ahead

NEW ROAD LAYOUT AHEAD

7014 V4
Permanent change in road layout ahead

NO HARD SHOULDER FOR 400 YARDS

7015
Temporary absence of hard shoulder over distance indicated (bespoke)

CROSSING NOT IN USE

7016
Zebra or signal controlled crossing temporarily out of use

PEDESTRIANS LOOK LEFT

7017
Direction in which pedestrians should look for approaching traffic

PEDESTRIANS LOOK BOTH WAYS

7017-1
Direction in which pedestrians should look for approaching traffic

MISCELLANEOUS WARNING , INFORMATORY AND REGULATORY SIGNS FOR ROAD WORKS

7017-2 Direction in which pedestrians should look for approaching traffic	7018 Direction of temporary route for pedestrians (bespoke)	7019 Light signals not in use	7020 Variable message sign ahead not in use or being tested	7021 Traffic on road ahead is being controlled by portable lights	7022 Traffic joining road being controlled by lights is not being controlled lights	7023 Vehicular traffic must not proceed
7024 Vehicular traffic may proceed	7031 Vehicular traffic must not proceed beyond sign during works	7201 V Restrictions owing to roadworks (bespoke)	7202 Two right hand lanes on a four lane carriage way closed to traffic ahead	7202 2Lanes Variable traffic flows (bespoke)	7202 3Lanes Variable traffic flows (bespoke)	7202 4Lanes Variable traffic flows (bespoke)
7203 Two lanes of carriageway open with offside contra flow working	7206 Centre lane closed traffic on offside of works travelling in opposite direction	7210 Diversion of 2 lanes to the other carriage way with restrictions (bespoke)	7215 Two lanes of traffic return to original carriageway	7221 Sharp bends ahead where traffic is diverted onto a temporary surface	7232 Return of traffic from hard shoulder and left lane of traffic to use 3 lanes	7234 Traffic on left lane to use hard shoulder traffic in centre to use right side lane
7250 Nearside traffic lane diverges at junction as part of temp. traffic management	7252 Traffic joining from the left as part of temporary traffic management	7253 Traffic joining from main carriageway as part of temporary traffic management	7254 Traffic lane joining from the left as part of temporary traffic management	7255 Additional traffic lane available ahead as part of temp. traffic management	7290 Mandatory speed limit ahead at road works	7291 Information on breakdown recovery services during road works
7292 Instructions to drivers on action to be taken before works	7293 Instructions to drivers on location on where to phone for assistance	7294 Temporary max speed in miles per hour advises (bespoke)	7301 Temporary acces to construction or road works site	7301-1 Temporary acces to construction or road works site	7301 V1 Temporary restrictions to works traffic	7301 V2 Temporary restrictions to vehicular traffic
7302 Temporary exit from a construction or road works site	7303 Direction to be taken by road works or construction traffic at junction	7304 Direction to be taken by road works or construction traffic at junction	7305 Direction to be taken by road works or construction traffic at junction	7306 Direction to be taken by road works or construction traffic to access site ahead	7307 Exit from a road works site	